



## CITY OF WORCESTER, MASSACHUSETTS



Administration & Finance  
Purchasing Division  
455 Main Street – Room 201  
Worcester, MA 01608  
(508) 799-1220  
[www.worcesterma.gov](http://www.worcesterma.gov)

March 31, 2022

To All Bidders:

Subject: **Bid No. 7771-W2, Resurfacing Streets (M22-6) / DPWP**

### **ADDENDUM NO. 2**

To Whom It May Concern:

With reference to our bid request relative to the above subject, please refer to the changes/modifications/clarifications to the original proposal request.

- **PLEASE SEE BELOW GENERAL BID CLARIFICATION**

#### **Streets with NO HOLD**

**AETNA ST** - MENDON ST. TO CUTLER ST.  
**EAST PARK TER** - OLEUM CT. TO NE END  
**EASTERN AVE** - BERKELEY ST. TO PROSPECT ST.  
**STERLING ST** - SEYMOUR ST. TO VIEW ST.  
**UPLAND ST** - UPLAND GARDENS DR. TO SW END

#### **Streets with Water HOLD – Water Main work needed**

**ALAMO ST** - LAMAR AVE. TO END  
**BRIDGEPORT ST** - ST. TO TAUNTON ST.  
**CARGILL AVE** - VERNON ST. TO STRATHMORE RD.  
**LUND ST** - ESTHER ST. TO LOUISE ST.  
**VERNON TER** - VERNON ST TO END

Attached is updated Resurfacing Project Locations with Upland St. and Vernon Terrace added to this list, refer to page 177 of 188.

Bidders are requested to acknowledge and/or include this addendum with bid. All other terms, conditions and specifications remain unchanged.

Very truly yours,

Christopher J. Gagliastro  
Purchasing Director

## **RESURFACING PROJECT LOCATIONS**

M22-6 STREETS/LOCATION	LENGTH	METHOD	HOLD	BINDER (12.5MM)	TOP (9.5MM)	TOP(12.5MM)
AETNA STREET - MENDON ST. TO CUTLER ST.	343'	PULVI - MILLING		2"	1.5"	
ALAMO STREET - LAMAR AVE. TO END	203'	GRIND - FULL DEPTH	WATER MAIN	2"	1.5"	
BRIDGEPORT STREET - GRANITE ST. TO TAUNTON ST.	620'	PULVI - MILLING	WATER MAIN	2"	1.5"	
CARGILL AVENUE - VERNON ST. TO STRATHMORE RD.	480'	PULVI - MILLING	WATER MAIN	2"	1.5"	
EAST PARK TERRACE - OLEUM CT. TO END	95'	PULVI - MILLING		2"	1.5"	
EASTERN AVENUE - BERKELEY ST. TO PROSPECT ST.	399'	PULVI - MILLING		2"	1.5"	
ENDICOTT STREET - VERNON ST. TO HARDING ST.	1872'	GRIND - FULL DEPTH	SPECTRUM	2.5"		2"
LUND STREET - ESTHER ST. TO LOUISE ST.	506'	PULVI - MILLING	WATER MAIN-SPECTRUM	2"	1.5"	
STERLING STREET - SEYMOUR ST. TO VIEW ST.	656'	PULVI - MILLING		2.5"		2"
UPLAND STREET - UPLAND GARDENS DR. TO CL	387'	GRIND - FULL DEPTH		2"	1.5"	
VERNON TERRACE - VERNON ST. TO END	222'	PULVI - MILLING	WATER MAIN	2.5"		2"

The above referenced streets will be reconstructed based on the degree of damage to existing surface and structures. It is the intent to rebuild as thoroughly as possible within budget limits and to meet existing conditions as closely as possible. On the streets that are to be pulvi-milled the existing bituminous concrete berm will be removed and replaced where needed as directed by the Contracting Officer and new bituminous concrete berm will be installed where no berm currently exists. On the streets that are to be ground full depth, the existing bituminous concrete berm will be removed and replaced where needed as directed by the Engineer.

It is envisioned that this work will be completed as quickly as possible. The Contractor will schedule all resurfacing related work only after all infrastructure work is completed on each street, and accepted by the City of Worcester.