



June 20, 2025

To All Bidders:

Subject: **Bid #: 8453-J6, Sewer Rehabilitation (S25-2) / DPWP**

ADDENDUM NO. 4

To Whom It May Concern:

With reference to our bid request relative to the above subject, please refer to the changes/modifications/clarifications to the original request.

Please see below questions received and responses from City:

1. Can the city provide a video for the 20"x30" pipe?
 - a. **The 20"x30" pipe has been removed from the contract. See Addendum No. 1.**
2. Can the city provide invert elevations for each manhole associated with this project?
 - a. **Approximate manhole depths are included in the contract drawings. Rim elevations are not available.**
3. It appears in the videos that certain pipe segments have concrete on the bottom of them and others it appears the invert is getting washed out and could have misplaced bricks. What are the cities expectations with these areas in terms of cleaning and finished product?
 - a. **Pipe cleaning shall be performed in accordance with Specification Section 02440, Sewer Cleaning and Inspection and Section 02428, Cured-in-Place Pipe. The Contractor is responsible for means and methods, which include clearing the line of obstructions that will interfere with the installation and long-term performance of the CIPP. The Contractor shall notify the Owner and Engineer of any unforeseen conditions that may impact acceptable installation of the CIPP. Notification would require a proposed approach, including any request for additional cost and time, for evaluation and approval prior to the start of the corresponding work. The Contractor may elect to place materials (sand, crushed stone, etc.) in any voids in the brick invert prior to installation of cured-in-place pipe to provide a smooth pipe invert after curing.**

Bidders are requested to acknowledge and/or include this addendum with submission. All other terms, conditions and specifications remain unchanged.

Very truly yours

Jerry Kucera
Buyer