<u>Installation of Fence – Worcester Police Department Headquarters:</u> <u>Goldsberry St Fence Line</u>

Worcester Police Department 9-11 Lincoln Square Worcester, MA 01608

Scope of Work:

AREA: Property fence line along Goldsberry St and along the WPD south property line that abuts private property parcel 47 Summer St (Jim and Son).

PREPARATION: All work areas and surrounding areas must be protected during construction. The contractor must also secure the work area with temporary barricades and/or cones to protect the public and city employees from construction activities and hazards created during the work process.

REMOVAL OF THE FOLLOWING: All fencing materials presently in place that will be replaced to include all top & bracing rails, terminal posts, line posts, and entrance way gate overhang rails. All concrete footings shall be removed unless removal causes damage to the existing asphalt, parking lot and/or city sidewalks.

INSTALLATION OF NEW FENCE: The contractor shall install 595 ft of commercial grade 6' high black chain link fence. The chain link material shall consist of the following:

- 72" 9GA black 2" mesh KK fusion bond chain link fabric
- 1-5/8" black PolyKote MG-40 top & bracing rail
- 2-7/8 black PolyKote MG-40 terminal post in concrete footing
- 2-3/8" black PolyKote MG-40 line post in concrete footing
- Post 10' on center in concrete footing; 8" wide x 36" deep
- Color plus fusion bond black coil spring bottom tension wire

*** Sono tubes and rebar cages **NOT** required ***

PRODUCT/MATERIALS: All materials required to complete the proper installation of the fence shall be supplied by the contractor.

CLEAN UP: The contractor is responsible for the removal and disposal of all unused material, trash, debris, tools, equipment, etc.

SCHEDULE: All work shall be conducted on Monday through Friday between the hours of 7:00 am and 4:00 pm. No work will be allowed outside of these time restrictions. All work areas must be secured during non-working hours. Any materials, tools, and miscellaneous items must be protected by the contractor. The owner will not be responsible for any items taken out of the work area.