



February 24, 2026

To All Bidders:

Subject: **Bid #: 8636-W6, Demolition – 19 Hilma Street / DIS-CDBG**

**ADDENDUM NO. 3**

To Whom It May Concern:

With reference to our bid request relative to the above subject, please refer to the changes/modifications/clarifications to the original request.

- **PRE-BID MEETING RESCHEDULED FROM TUESDAY, FEBRUARY 24 TO FRIDAY, FEBRUARY 27, 2026 AT 10:00 AM**
- **PLEASE NOTE: ACCESS TO THE INTERIOR OF THE BUILDING IS NOT ALLOWED PER BUILDING COMMISSIONER**
- **PLEASE SEE QUESTIONS RECEIVED AND RESPONSES FROM CITY:**
- Are the utility services to be disconnected, cut, and capped on the property or in the street?  
Answer: Please see updated specification section below.

**SANITARY AND DRAINAGE CONNECTIONS AND ALL OTHER UTILITIES**

The Contractor shall assure that all utilities and city services (e.g. water, sewer, gas, electricity, etc.) are disconnected and appropriate steps taken to protect the Contractor's interest in the property (e.g. capping of disconnected sewers) prior to the scheduling of demolition. The Contractor shall excavate, break and seal all drainage and sanitary sewer connections at the street line of the building lot (property line). Seals within the building will not be accepted. The sealed pipes and drains shall not be backfilled until they have been inspected and approved by the City of Worcester's Department of Public Works. *All other utilities (water, gas, electric, cable) shall be cut at the pole or underground terminal, off the property line.*

Bidders are requested to acknowledge and/or include this addendum with submission. All other terms, conditions and specifications remain unchanged.

Christopher J. Gagliastro  
Purchasing Director