



February 13, 2026

To All Bidders:

Subject: **Bid No. 8637-M6, Lake View Playground Improvements / DPRC**

ADDENDUM NO. 2

To Whom It May Concern:

With reference to our bid request relative to the above subject, please refer to the changes/modifications/clarifications to the original proposal request.

General Bid Questions:

Question1: Special Conditions Article 41 “DPRC Standard Security Camera Appurtenances” paragraph B states to include in base bid furnishing, installing and testing 2000LF of fiber optic cable. Why is the quantity 2000LF when it scales off to be more like 550LF? Can we carry in our base bid the actual quantity required?

Answer: **Include in bid the quantity that is needed to furnish and install as required for a complete operating system.**

Question2: The same paragraph referenced above calls for the contractor to carry all vertical splices to cameras. Are we to carry vertical splices at all 8 pedestrian and sports lighting pole? Please be aware that the splicing is very costly, and it seems unlikely that every pole will have a camera.

Answer: **Yes, cameras are planned for all eight locations, also refer to Sheet E2 for locations of corresponding eight communication handholes.**

Question3: General Note 1 on drawing E-2 calls for 175' of conduit and cabling from the electrical cabinet to the utility pole. The actual distance from the cabinet to the utility pole is approximately 40' plus say 30' up the utility pole. Do we need to carry 175' in our bids when it is more like 70'?

Answer: **Include in bid the quantity that is needed to furnish and install as required for a complete operating system.**

Question4: Do the Holophane light poles require Field Installed Auxiliary Wire Exits and SiteLink TracNuts? The detail on drawing E-3 does not show these items.

Answer: **Yes, they are required hardware for the complete install of security cameras on the six pedestrian light poles.**



The City of **WORCESTER**

Administration & Finance – Purchasing Division
Christopher J. Gagliastro, MCPPO – Purchasing Director
455 Main Street, Room 201, Worcester, MA 01608
P | 508-799-1220
purchasing@worcesterma.gov

Question5: Are National Grid charges for the new electrical service paid by the City of Worcester?

Answer: Yes

Question6: Are City of Worcester electrical permit fees waived for this project?

Answer: No

Question6: Please confirm if the DPRC standard precast handholes for electric, and communication networks are to be used. If so please provide the DPRC drawings for standard handholes required.

Answer: Project standard Handholes attached.

Bidders are requested to acknowledge and/or include this addendum with submission. All other terms, conditions and specifications remain unchanged.

Very truly yours,

Stephen R. McDonald
Assistant Purchasing Director

OSTROW ELECTRIC COMPANY



Contractors • Engineers

9 MASON STREET, WORCESTER, MASSACHUSETTS 01609

ESTABLISHED 1939 TEL. 508-754-2641 FAX. 508-757-1645

ELECTRICAL PRODUCT SUBMITTALS

For

South Worcester Playground
Phase 1 & 2 - 2018
Worcester, MA

ENGINEER

Engineering Advantage, Inc.
880 Main Street, 5th Floor
Waltham, MA 02451

GENERAL CONTRACTOR

Busy Bee Nursery
57 Broad Street, Route 68
Jefferson, MA 01522

SUBMITTED BY:

Ostrow Electric Company
9 Mason Street
Worcester, MA 01609

DATE

August 14, 2018

OK approved as noted

08-14-2018

SUBMITTAL

Electrical

MATERIAL


Handholes

SUBMISSION


Resubmittal

Remarks: Submittal has been reviewed by Ostrow Electric Company and has been found, to the best of our knowledge, to conform to contract documents.


William H. Robinson, Jr.
Project Manager




V5665 Frame




PLAN VIEW



FRAME SECTION



FRAME SECTION



TOP FLANGE VIEW

Product Number
45665010
Design Features
-Materials
Gray Iron (CL35B)
-Design Load
Heavy Duty
-Open Area
n/a
-Coating
Undipped
- Designates Machined Surface

Certification
-ASTM A48

Country of Origin: USA

Drawing Revision
05/02/2003 Designer: DEW
09/08/2016 Revised By: DVD


Disclaimer
Weights (lbs./kg) dimensions (inches/mm) and drawings provided for your guidance. We reserve the right to modify specifications without prior notice.
CONFIDENTIAL: This drawing is the property of EJ GROUP, Inc., and embodies confidential information, registered marks, patents, trade secret information, and other know how that is the property of EJ GROUP, Inc. Copyright © 2012 EJ GROUP, Inc. All rights reserved.

Contact
800 626 4653
ejco.com


V6665 Cover



1 1/4" SHARP FACE
+ GOTHIC + COMMUNICATON 24x36



COVER TOP VIEW




COVER SECTION

Product Number
46665022
Design Features
-Materials
Gray Iron (CL35B)
-Design Load
Heavy Duty
-Open Area
N/A
-Coating
Undipped
...: Designates Machined Surface

Certification
-ASTM A48
-

Country of Origin: USA



COVER SECTION


PROD NO.
MO/DY/YR X
ASTM A48
CL35B

(4) TYPE 4 STAINLESS STEEL PICKBARS
PICKBAR DETAIL

Drawing Revision
06/12/2006 Designer: TCL
6/3/2015 Revised By: DAE

Disclaimer
Weights (lbs./kg) dimensions (inches/mm) and drawings provided for your guidance. We reserve the right to modify specifications without prior notice.

CONFIDENTIAL: This drawing is the property of EJ GROUP, Inc., and embodies confidential information, registered marks, patents, trade secret information, and/or know how that is the property of EJ GROUP, Inc. Copyright © 2012 EJ GROUP, Inc. All rights reserved.
Contact
800 626 4653
eico.com



Dim 'H'	Est Weight:	P/N:
20"	600 Lbs	HH-12X24BOSSH
33"	1,000 Lbs	HH-12X24BOSTALL

General Notes

1. Concrete: $f_c = 4,000 \text{ psi}$ @ 28 Days Minimum
2. Steel Reinforcement Conforms to Latest ASTM Specification: ASTM A-615, Grade 60 Black Deformed Bars
3. Boston Standard Pull Box

Phoenix
Precast
Products

12" x 24" Electric
Handhole

EJIW EAST JORDAN

IRON WORKS EST. 1883
800-626-4653

www.ejiw.com

MADE IN USA
PRODUCT NUMBER

00801312

CATALOG NUMBER

8013Z1

LV1325 FRAME

LOAD RATING


HEAVY DUTY

COATING

UNDIPPED

SPECIFICATION

FRAME-GRAY IRON
ASTM A48 CL35B



CONFIDENTIAL: This drawing is the property of East Jordan Iron Works, Inc. and embodies confidential information, trade secret information, and/or know how that is the property of East Jordan Iron Works, Inc. ©Copyright 2009 East Jordan Iron Works, Inc.

EJIW EAST JORDAN

IRON WORKS EST. 1883

800-626-4653

www.ejiw.com

MADE IN USA

PRODUCT NUMBER

00801321

CATALOG NUMBER

8013A

**MANHOLE
COVER**

LOAD RATING

HEAVY DUTY

COATING

UNDIPPED

SPECIFICATION

COVER - GRAY IRON
ASTM A48 CL35B

OPEN AREA

N/A



✓ DESIGNATES
MACHINED SURFACE

DRAWN
SBB



DATE
05/28/08
LAST REVISED
SBB

DATE
04/13/09

FUTURE TAG OPTIONS
(REF. 8016 TAGS)



SECTION A-A



SECTION B-B

CONFIDENTIAL: This drawing is the property of East Jordan Iron Works, Inc. and embodies confidential information, trade secret information, and/or know how that is the property of East Jordan Iron Works, Inc. ©Copyright 2008 East Jordan Iron Works, Inc.