



The City of  
**WORCESTER**

Administration & Finance – Purchasing Division  
Christopher J. Gagliastro, MCPPO – Purchasing Director  
455 Main Street, Room 201, Worcester, MA 01608  
P | 508-799-1220  
[purchasing@worcesterma.gov](mailto:purchasing@worcesterma.gov)

March 23, 2026

To All Bidders:

Subject: **Bid No. 8649-M6 – Resurfacing Various Streets (M25-3) / DPW**

**ADDENDUM NO. 2**

To Whom It May Concern:

With reference to our bid request relative to the above subject, please refer to the changes/modifications/clarifications to the original proposal request.

**General Bid Clarification:**

1. Please use the updated P-sheets attached to this document.

**Questions Received by this Office and Answers from the City:**

1. Item 806.2 2 Inch Electrical Conduit
  - B. Materials - The Standard Specifications call for Rigid Metal Conduit.  
\*Please confirm that the City desires RM Conduit to be installed under this contract.
  - E. Installation - The Standard Specifications require a minimum of 4 inches of concrete on all sides when crossing streets and driveways. Without any plans to reference, it is not possible to determine how much concrete will be required under this item.  
\*Please provide a contract bid item for concrete encasement.  
**A: Item 806.2000 has been removed and replaced with Item 804.2000. The material used is 2" SCH 80 PVC as specified. NO concrete needed for encasement for this item in this contract because road, sidewalks, and driveways will be compacted during construction**
2. The above-referenced project lists proposal items 435.1 Random Crack Sealing, and 490 Polymer and Crumb Rubber Modified Sealant. Where does the City propose to use these items on streets that are to be reclaimed?  
**A: The Crack seal has been narrowed to a single item. It is meant to be used as requested by the engineer at: asphalt joints at the back of driveways and the joints at the limits of paving, and for general crack seal as needed.**

Bidders are requested to acknowledge and/or include this addendum with submission. All other terms, conditions and specifications remain unchanged.

Very truly yours,

Stephen R. McDonald  
Assistant Purchasing Director

## M25-3 Resurfacing

THE BIDDER MUST FILL IN THESE UNIT PRICES. Also carry out all extensions and fill in "Computed Totals."  
 In case of error or discrepancies, UNIT PRICES govern and written works take precedence over figures.

ITEM NUMBER AND DESCRIPTION	ESTIMATED QUANTITY	COMPUTED TOTALS
100.0000 CLEARING & GRUBBING		
	Dollars	0.60 \$
(\$ ) AC		
104.0000 TREE REMOVAL (LESS THAN 24 INCHES) INCLUDING STUMP		
	Dollars	2.00 \$
(\$ ) EA		
106.0000 TREE REMOVAL (24 INCHES & OVER) INCLUDING STUMP		
	Dollars	5.00 \$
(\$ ) EA		
107.0000 STREET TREE REPLACEMENT		
	Dollars	26.00 \$
(\$ ) EA		
109.0000 STUMP REMOVED (GREATER THAN 24 INCHES)		
	Dollars	7.00 \$
(\$ ) EA		
110.0000 PINE BARK MULCH		
	Dollars	5.00 \$
(\$ ) CY		
113.0000 TREE PROTECTION		
	Dollars	39.00 \$
(\$ ) EA		
116.0000 EXCAVATION		
	Dollars	122.00 \$
(\$ ) CY		
125.0000 SAND BORROW		
	Dollars	240.00 \$
(\$ ) CY		

## M25-3 Resurfacing

ITEM NUMBER AND DESCRIPTION	ESTIMATED QUANTITY	COMPUTED TOTALS
126.0000 GRAVEL BORROW		
	Dollars	188.00 \$
(\$ ) CY		
128.0000 SCREENED LOAM BORROW		
	Dollars	1,169.00 \$
(\$ ) CY		
130.0000 CRUSHED STONE 3/4 INCH		
	Dollars	265.00 \$
(\$ ) CY		
132.0000 CRUSHED STONE 1-1/2 INCH		
	Dollars	265.00 \$
(\$ ) CY		
150.0000 FURNISH AND SPREAD CALCIUM CHLORIDE		
	Dollars	21,140.00 \$
(\$ ) LB		
156.0000 SEEDING		
	Dollars	4,102.00 \$
(\$ ) SY		
220.0600 TRENCH EXCAVATION AND BACKFILL, FURNISH AND INSTALL 6" PVC		
	Dollars	40.00 \$
(\$ ) LF		
235.0000 CATCH BASIN FRAME & GRATE		
	Dollars	38.00 \$
(\$ ) EA		
236.0000 MANHOLE FRAME & COVER		
	Dollars	78.00 \$
(\$ ) EA		
242.0000 CATCH BASIN REBUILD "D" FRAME TO SQUARE FRAME		
	Dollars	11.00 \$
(\$ ) EA		

## M25-3 Resurfacing

ITEM NUMBER AND DESCRIPTION	ESTIMATED QUANTITY	COMPUTED TOTALS
245.1000 EXISTING GRANITE INLET STONE REMOVE & RESET		
	Dollars	35.00 \$
(\$ ) EA		
246.0000 8 INCH GREEN TRAPS		
	Dollars	51.00 \$
(\$ ) EA		
249.0000 CATCH BASIN CLEANING		
	Dollars	58.00 \$
(\$ ) EA		
250.0000 MANHOLE FRAMES, REMOVE, PLATE & RETAIN		
	Dollars	92.00 \$
(\$ ) EA		
252.1000 MANHOLE ADJUSTMENT 12 INCH OR LESS GRAVEL		
	Dollars	18.00 \$
(\$ ) EA		
252.2000 MANHOLE ADJUSTMENT 12 INCH OR LESS RIGID		
	Dollars	2.00 \$
(\$ ) EA		
253.1000 MANHOLE ADJUSTMENT OVER 12 INCH GRAVEL		
	Dollars	30.00 \$
(\$ ) VI		
253.2000 MANHOLE ADJUSTMENT OVER 12 INCH RIGID		
	Dollars	12.00 \$
(\$ ) VI		
254.1000 CATCH BASIN ADJUST TO LINE AND/OR GRADE 12 INCH OR LESS, GRAVEL		
	Dollars	27.00 \$
(\$ ) EA		

## M25-3 Resurfacing

ITEM NUMBER AND DESCRIPTION	ESTIMATED QUANTITY	COMPUTED TOTALS
254.2000 CATCH BASIN ADJUST TO LINE AND/OR GRADE 12 INCH OR LESS, RIGID  <hr style="width: 40%; margin-left: 0;"/> Dollars (\$ ) EA	1.00	\$ <hr style="width: 80%; margin-left: 0;"/>
255.1000 CATCH BASIN ADJUST TO LINE AND/OR GRADE 12 INCH OR OVER, GRAVEL  <hr style="width: 40%; margin-left: 0;"/> Dollars (\$ ) VI	24.00	\$ <hr style="width: 80%; margin-left: 0;"/>
255.2000 CATCH BASIN ADJUST TO LINE AND/OR GRADE 12 INCH OR OVER, RIGID  <hr style="width: 40%; margin-left: 0;"/> Dollars (\$ ) VI	12.00	\$ <hr style="width: 80%; margin-left: 0;"/>
260.0600 6 INCH SUBDRAIN COMPLETE  <hr style="width: 40%; margin-left: 0;"/> Dollars (\$ ) LF	40.00	\$ <hr style="width: 80%; margin-left: 0;"/>
261.0000 REPAIR, REPLACE OR RELOCATE EXISTING DRAINS  <hr style="width: 40%; margin-left: 0;"/> Dollars (\$ ) LF	20.00	\$ <hr style="width: 80%; margin-left: 0;"/>
304.0300 ADJUST CURB STOP TO GRADE  <hr style="width: 40%; margin-left: 0;"/> Dollars (\$ ) EA	88.00	\$ <hr style="width: 80%; margin-left: 0;"/>
304.0400 REPLACING 4" - 12" GATE VALVE BOX, GRAVEL BASE  <hr style="width: 40%; margin-left: 0;"/> Dollars (\$ ) EA	54.00	\$ <hr style="width: 80%; margin-left: 0;"/>
304.0600 REMOVE AND RETAIN WATER BOX  <hr style="width: 40%; margin-left: 0;"/> Dollars (\$ ) EA	83.00	\$ <hr style="width: 80%; margin-left: 0;"/>
304.0700 RETURN AND RESET WATER BOX  <hr style="width: 40%; margin-left: 0;"/> Dollars (\$ ) EA	22.00	\$ <hr style="width: 80%; margin-left: 0;"/>

## M25-3 Resurfacing

ITEM NUMBER AND DESCRIPTION	ESTIMATED QUANTITY	COMPUTED TOTALS
304.0800 WATER BOX ADJUST TO GRADE, GRAVEL BASE		
	Dollars	8.00 \$
(\$ ) EA		
304.1000 LOWER STREET SERVICE BOX		
	Dollars	92.00 \$
(\$ ) EA		
310.6000 HYDRANT PAINTING		
	Dollars	15.00 \$
(\$ ) EA		
404.0000 PULVI-MILLING		
	Dollars	23,060.00 \$
(\$ ) SY		
405.0000 STRAIGHT CURB (VA-4)		
	Dollars	1,540.00 \$
(\$ ) LF		
408.0000 CIRCULAR CURB (10' RADIUS & OVER) (VA-4)		
	Dollars	480.00 \$
(\$ ) LF		
409.0000 CIRCULAR CURB (10" RADIUS & UNDER) (VA-4)		
	Dollars	480.00 \$
(\$ ) LF		
410.0000 CIRCULAR CORNER (WORCESTER STANDARD)		
	Dollars	54.00 \$
(\$ ) EA		
416.0000 CURB REMOVE AND RESET		
	Dollars	3,850.00 \$
(\$ ) LF		

## M25-3 Resurfacing

ITEM NUMBER AND DESCRIPTION	ESTIMATED QUANTITY	COMPUTED TOTALS
422.1000 SUPERPAVE 9.5 MM LEVEL 2		
	Dollars	2,410.00 \$
(\$ ) TN		
422.2000 SUPERPAVE 12.5 MM LEVEL 2		
	Dollars	3,090.00 \$
(\$ ) TN		
424.0000 BITUMINOUS CONCRETE DRIVEWAY & VARIOUS AREA		
	Dollars	150.00 \$
(\$ ) TN		
430.0000 EXISTING BITUMINOUS CONCRETE DRIVEWAY REPAIR		
	Dollars	1,820.00 \$
(\$ ) SY		
432.0000 EXISTING BITUMINOUS CONCRETE SIDEWALKS REPAIR		
	Dollars	225.00 \$
(\$ ) SY		
435.0000 HOT POURED RUBBERIZED ASPHALT SEALER		
	Dollars	2,195.00 \$
(\$ ) LF		
438.5000 BITUMINOUS CONCRETE BERM REPAIR		
	Dollars	6,260.00 \$
(\$ ) LF		
441.0000 REPLACING BITUMINOUS CONCRETE SIDEWALK W/CONCRETE SIDEWALK 4 INCH		
	Dollars	1,650.00 \$
(\$ ) SY		
442.0000 CONCRETE SIDEWALK REPAIR		
	Dollars	1,980.00 \$
(\$ ) SY		

## M25-3 Resurfacing

ITEM NUMBER AND DESCRIPTION	ESTIMATED QUANTITY	COMPUTED TOTALS
443.0000 REPLACING BITUMINOUS CONCRETE DRIVEWAY W/CONCRETE DRIVEWAY 6 INCH		
_____ Dollars	710.00	\$ _____
(\$ _____) SY		
446.0000 CONCRETE DRIVEWAY REPAIR		
_____ Dollars	100.00	\$ _____
(\$ _____) SY		
446.1000 CLASS B CONCRETE FOR ROADWAY BASE (3,500 P.S.I. 1-1/2 520)		
_____ Dollars	265.00	\$ _____
(\$ _____) CY		
447.0200 EXISTING BRICK SIDEWALKS AND DRIVEWAYS WITH GRAVEL BASE – REMOVE & RESET		
_____ Dollars	119.00	\$ _____
(\$ _____) SY		
448.0000 WORCESTER HIGHWAY MONUMENT		
_____ Dollars	18.00	\$ _____
(\$ _____) EA		
450.0000 BOUNDS, REMOVE & RESET		
_____ Dollars	10.00	\$ _____
(\$ _____) EA		
454.0000 WHEELCHAIR RAMP CEMENT CONCRETE - 6" THICK WITH DETECTABLE WARNING PANELS		
_____ Dollars	625.00	\$ _____
(\$ _____) SY		
456.0000 CONCRETE STEP (COMPLETE IN PLACE)		
_____ Dollars	5.00	\$ _____
(\$ _____) EA		
467.0000 REMOVE AND REPLACE EXISTING GUARDRAIL		
_____ Dollars	602.00	\$ _____
(\$ _____) LF		

## M25-3 Resurfacing

ITEM NUMBER AND DESCRIPTION	ESTIMATED QUANTITY	COMPUTED TOTALS
472.0000 WIRE FENCE, REMOVE AND RESET		
_____ Dollars	160.00	\$ _____
(\$ _____) LF		
483.0000 REPLACING GAS BOX, GRAVEL BASE		
_____ Dollars	7.00	\$ _____
(\$ _____) EA		
485.0000 REMOVE AND RETAIN GAS BOX		
_____ Dollars	15.00	\$ _____
(\$ _____) EA		
486.0000 RETURN AND RESET GAS BOX		
_____ Dollars	9.00	\$ _____
(\$ _____) EA		
487.0000 GAS BOX ADJUST TO GRADE, GRAVEL BASE		
_____ Dollars	4.00	\$ _____
(\$ _____) EA		
503.0000 12 INCH REFLECTORIZED WHITE LINE (THERMOPLASTIC)		
_____ Dollars	1,020.00	\$ _____
(\$ _____) LF		
520.0000 WARNING AND REGULATORY SIGNS		
_____ Dollars	28.00	\$ _____
(\$ _____) EA		
522.0000 TYPE "B" STREET NAME SIGNS		
_____ Dollars	17.00	\$ _____
(\$ _____) EA		
523.0000 TRAFFIC SIGN POLES		
_____ Dollars	18.00	\$ _____
(\$ _____) EA		
530.0000 POLE PAINTING		
_____ Dollars	3.00	\$ _____
(\$ _____) EA		

## M25-3 Resurfacing

ITEM NUMBER AND DESCRIPTION	ESTIMATED QUANTITY	COMPUTED TOTALS
804.2000 2-INCH ELECTRICAL CONDUIT (FOOT) SCH 40 PVC		
	Dollars	1,400.00 \$
(\$ ) LF		
810.3000 PULL BOX 12"X24" (SD 2.030) FOR SIGNAL CABLE		
	Dollars	5.00 \$
(\$ ) EA		
810.4000 PULL BOX 12"X12" (SD 2.031) FOR INTERCONNECTION CABLE		
	Dollars	1.00 \$
(\$ ) EA		
812.2000 LIGHT STANDARD FOUNDATION CONCRETE (EACH)		
	Dollars	5.00 \$
(\$ ) EA		
813.3200 CONDUCTOR #6 AWG (FOOT)		
	Dollars	2,750.00 \$
(\$ ) LF		
814.0000 REMOVE AND RESET STREET LIGHT POLE		
	Dollars	5.00 \$
(\$ ) EA		
821.0000 STREET LIGHT		
	Dollars	2.00 \$
(\$ ) EA		
900.0000 Lump Sum Reserve		
two hundred ninety-nine thousand two hundred thirty-three and xx / 100	Dollars	\$ 299,233.00
953.2020 SILT SACK		
	Dollars	57.00 \$
(\$ ) EA		

# M25-3 Resurfacing

## TOTAL BID PRICE INCLUDING CONTINGENCY

\_\_\_\_\_ Dollars                      and                      \_\_\_\_\_ Cents  
(amount in words)

\$ \_\_\_\_\_  
(amount in figures)

This proposal is based on provisions of the following addenda:

No. \_\_\_\_\_

No. \_\_\_\_\_

No. \_\_\_\_\_

No. \_\_\_\_\_

All amounts and totals given above will be subject to verification by the City. In case of variation between Unit Bid Price and Totals shown by the Bidder, the Unit Price written in words will be considered to be the bid.

The City reserves the right to reject any and all bids, wholly or in part, and to make awards in a manner deemed in the best interests of the City.

The above estimated quantities form an approximate statement of the extent of the work to be done, based upon the estimate of the Contracting Officer. The City does not expressly or by implication agree that the actual quantity of work will correspond therewith, but reserves the right to increase or decrease the quantity of any class or portion of the work, as may be deemed necessary by the Contracting Officer.