



March 20, 2026

To All Bidders:

Subject: **Bid No. 8652-J6 – Resurfacing – Various Streets (M25-6) / DPW**

ADDENDUM NO. 2

To Whom It May Concern:

With reference to our bid request relative to the above subject, please refer to the changes/modifications/clarifications to the original proposal request.

General Bid Clarification:

1. Please use the updated P-sheets attached to this document.

Questions Received by this Office and Answers from the City:

1. Please provide Water Service Worksheets which list the streets, addresses, service sizes, materials, year, Item Number & Descriptions.
 - a. See Attached Service worksheets
2. Please provide plans showing the proposed PVC conduit and street light work.
 - a. Plans will not be provided pre bid. Please see attached quantities by street.
3. On which streets are the Clearing & Grubbing intended to be used?
 - a. Potentially on Drury Lane
4. What is Item 402 intended to be used for and on which street(s)?
 - a. Item removed
5. Do any of the resurfacing contracts have any streets with utility holds? If so can you list the streets that have utility holds?
 - a. First Street – Hold for Water Department – Services, pressure system requiring service work and 1 relay.



6. Are there any plans for the 2” conduit, pull boxes and any other light work? Can you list the specific streets with quantities receiving these items?
 - a. At this time there are no designed plans for proposed streetlight work. Only the roads with aluminum streetlight poles or black decorative poles that utilize underground direct bury wiring are expected to be the candidates for all streetlight items. Roads with wooden poles with overhead wires are not expected to use any of the streetlight items. See attached estimated quantities by street.
7. With all of the street light work is it going to be mandatory to keep the existing lights operational while the new conduit, pull boxes, and light bases get installed? If so does the city have a plan on how to achieve this?
 - a. Yes, it is mandatory to keep all streetlighting operational throughout the entire construction process (not just during streetlight item installation). In previous cases, Contractors have installed conduit, installed pull boxes, installed new foundations while keeping all the existing lights operational. In those same previous cases, contractors conducted the final stages of streetlight work by switching over the wiring during daytime hours so that the new lights were operational that same night. This same concept is expected to be followed.
8. Does the city already have permitting for where the city plans to make any new service connections concerning the light work? If not does the city see this as a potential hold up?
 - a. The awarded contractor will need to coordinate with the utility contractor. The only permit required is to do the punchout for access which is in the scope of work for the utility company and does not have a fee.
9. Are there any plans for the water work? Item #'s 301.01, 304.1, & 309.3. Are these quantities broken down by street? If so can these quantities be given? Will all of the water work be available once the notice to proceed is awarded?
 - a. See Attached water takeoff sheets. Availability will be discussed on the pre construction meeting. For bidding purposes, assume they will not be immediately available.
10. Item 125 Sand Borrow, where does city plan to use this item? Is it in conjunction with the conduit items?
 - a. City is expecting to use Item125 Sand Borrow on roads that require water work.
11. M25-6 has 8,870 sy of fine grading? Where is the city planning to use this item?
 - a. Item removed



The City of
WORCESTER

Administration & Finance – Purchasing Division
Christopher J. Gagliastro, MCPPO – Purchasing Director
455 Main Street, Room 201, Worcester, MA 01608
P | 508-799-1220
purchasing@worcesterma.gov

12. Item 434 sawing asphalt pavement. The quantities vary greatly between contracts? Can you explain why the quantities vary so much between contracts? M25-3 2,640' item 434, M25-4 150' item 434, M25-5 200' item 434, M25-6 3,150' item 437F
 - a. **Item removed**

Bidders are requested to acknowledge and/or include this addendum with submission. All other terms, conditions and specifications remain unchanged.

Very truly yours,

Jerry Kucera
Buyer

Service Worksheet

Street(limits): **First Street (#1 First Street to #59 First Street)**

Address	Service No.	Size	Material	Year	Item Numbers & Descriptions							
					301.01 CofS(ft.)	314.3 Abandon	314.5 Abandon	309.2 C.S.	309.3 3/4"-1" CICS	309.4 1 1/4"-2" CICS	304.10 L.B.	
4	20030	3/4	IRON	1914	10				1			1
10	31615	3/4	COPPER	1939	10				1			1
12	31624	3/4	IRON	1939	10				1			1
13	36899	3/4	COPPER	1952						1		1
14	20023	3/4	COPPER	1914						1		1
18	42432	3/4	COPPER	1965						1		1
20	42433	3/4	COPPER	1965						1		1
22	39720	3/4	COPPER	1958						1		1
28 (Tapped off Center St)	43922	1	PLASTIC	1973								1
30 (Tapped off Center St)	39928	3/4	COPPER	1958						1		1
31	33724	3/4	COPPER	1947						1		1
32	45647	1	PLASTIC	1984								1
34	45648	1	PLASTIC	1984								1
38	44813	1	PLASTIC	1981								1
42	33714	3/4	COPPER	1947						1		1
45	33815	3/4	COPPER	1947						1		1
46	35698	3/4	COPPER	1950						1		1
48	33569	3/4	COPPER	1947						1		1
53	45636	1	PLASTIC	1984								1
55	45637	1	PLASTIC	1984								1
2 (Tapped on First St)	45634	1	PLASTIC	1985								1
4 (Tapped on First St)	45635	1	PLASTIC	1985								1
57	45638	1	PLASTIC	1984								1
59	45639	1	PLASTIC	1984								1
Totals					30	0	0	3	11	0		23

NOTES:

- CofS(ft.) - Change of Service on City Property (estimated footage)
- C.S. - Curb Stop Installed during CofS
- C.I.C.S. - Cut-In Curb Stop
- L.B. - Lower Street Box

CDF

Service Worksheet

Street(limits): **William Street (#3 to #112)**

Address	Service No.	Size	Material	Year	Item Numbers & Descriptions						
					301.01 CofS(ft.)	314.3 Abandon	314.5 Abandon	309.2 C.S.	309.3 3/4"-1" CICS	309.4 1 1/4"-2" CICS	304.10 L.B.
66	16802	3/4	Copper	1909					1		1
79	13196	3/4	Copper	1899					1		1
81	27737	3/4	Copper	1926					1		1
84	15534	3/4	Copper	1906					1		1
85	22748	1	Plastic	1920					1		1
87	28336	1	Plastic	1927							1
89	37624	3/4	copper	1953					1		1
Totals					0	0	0	0	6	0	7

NOTES:

- CofS(ft.) - Change of Service on City Property (estimated footage)
- C.S. - Curb Stop Installed during CofS
- C.I.C.S. - Cut-In Curb Stop
- L.B. - Lower Street Box

 CDF

Street Light Work		
Contract M25-6		
	Hadwen Ln	
Item	Quantity	Unit
806.2000	1700	feet
810.3000	9	each
812.2000	9	feet
813.3200	3300	feet
814.0000	9	each

M25-6 Resurfacing

THE BIDDER MUST FILL IN THESE UNIT PRICES. Also carry out all extensions and fill in "Computed Totals."
 In case of error or discrepancies, UNIT PRICES govern and written works take precedence over figures.

ITEM NUMBER AND DESCRIPTION	ESTIMATED QUANTITY	COMPUTED TOTALS
100.0000 CLEARING & GRUBBING		
	Dollars	0.80 \$
(\$) AC		
104.0000 TREE REMOVAL (LESS THAN 24 INCHES) INCLUDING STUMP		
	Dollars	12.00 \$
(\$) EA		
106.0000 TREE REMOVAL (24 INCHES & OVER) INCLUDING STUMP		
	Dollars	9.00 \$
(\$) EA		
107.0000 STREET TREE REPLACEMENT		
	Dollars	23.00 \$
(\$) EA		
108.0000 STUMP REMOVED (LESS THAN 24 INCHES)		
	Dollars	1.00 \$
(\$) EA		
109.0000 STUMP REMOVED (GREATER THAN 24 INCHES)		
	Dollars	1.00 \$
(\$) EA		
113.0000 TREE PROTECTION		
	Dollars	7.00 \$
(\$) EA		
116.0000 EXCAVATION		
	Dollars	80.00 \$
(\$) CY		
125.0000 SAND BORROW		
	Dollars	45.00 \$
(\$) CY		

M25-6 Resurfacing

ITEM NUMBER AND DESCRIPTION	ESTIMATED QUANTITY	COMPUTED TOTALS
126.0000 GRAVEL BORROW		
	Dollars	130.00 \$
(\$) CY		
128.0000 SCREENED LOAM BORROW		
	Dollars	313.00 \$
(\$) CY		
130.0000 CRUSHED STONE 3/4 INCH		
	Dollars	318.00 \$
(\$) CY		
132.0000 CRUSHED STONE 1-1/2 INCH		
	Dollars	318.00 \$
(\$) CY		
150.0000 FURNISH AND SPREAD CALCIUM CHLORIDE		
	Dollars	300.00 \$
(\$) LB		
156.0000 SEEDING		
	Dollars	2,730.00 \$
(\$) SY		
235.0000 CATCH BASIN FRAME & GRATE		
	Dollars	32.00 \$
(\$) EA		
236.0000 MANHOLE FRAME & COVER		
	Dollars	37.00 \$
(\$) EA		
245.0000 GRANITE INLET STONE		
	Dollars	1.00 \$
(\$) EA		
245.1000 EXISTING GRANITE INLET STONE REMOVE & RESET		
	Dollars	46.00 \$
(\$) EA		

M25-6 Resurfacing

ITEM NUMBER AND DESCRIPTION	ESTIMATED QUANTITY	COMPUTED TOTALS
246.0000 8 INCH GREEN TRAPS		
_____ Dollars	33.00	\$ _____
(\$ _____) EA		
249.0000 CATCH BASIN CLEANING		
_____ Dollars	46.00	\$ _____
(\$ _____) EA		
250.0000 MANHOLE FRAMES, REMOVE, PLATE & RETAIN		
_____ Dollars	51.00	\$ _____
(\$ _____) EA		
252.1000 MANHOLE ADJUSTMENT 12 INCH OR LESS GRAVEL		
_____ Dollars	11.00	\$ _____
(\$ _____) EA		
252.2000 MANHOLE ADJUSTMENT 12 INCH OR LESS RIGID		
_____ Dollars	1.00	\$ _____
(\$ _____) EA		
253.1000 MANHOLE ADJUSTMENT OVER 12 INCH GRAVEL		
_____ Dollars	12.00	\$ _____
(\$ _____) VI		
254.1000 CATCH BASIN ADJUST TO LINE AND/OR GRADE 12 INCH OR LESS, GRAVEL		
_____ Dollars	19.00	\$ _____
(\$ _____) EA		
254.2000 CATCH BASIN ADJUST TO LINE AND/OR GRADE 12 INCH OR LESS, RIGID		
_____ Dollars	2.00	\$ _____
(\$ _____) EA		
255.1000 CATCH BASIN ADJUST TO LINE AND/OR GRADE 12 INCH OR OVER, GRAVEL		
_____ Dollars	12.00	\$ _____
(\$ _____) VI		

M25-6 Resurfacing

ITEM NUMBER AND DESCRIPTION	ESTIMATED QUANTITY	COMPUTED TOTALS
301.0100 1" Polyethylene Tubing		
_____ Dollars	1,100.00	\$ _____
(\$ _____) LF		
304.0300 ADJUST CURB STOP TO GRADE		
_____ Dollars	82.00	\$ _____
(\$ _____) EA		
304.0400 REPLACING 4" - 12" GATE VALVE BOX, GRAVEL BASE		
_____ Dollars	34.00	\$ _____
(\$ _____) EA		
304.0600 REMOVE AND RETAIN WATER BOX		
_____ Dollars	43.00	\$ _____
(\$ _____) EA		
304.0700 RETURN AND RESET WATER BOX		
_____ Dollars	9.00	\$ _____
(\$ _____) EA		
304.0800 WATER BOX ADJUST TO GRADE, GRAVEL BASE		
_____ Dollars	21.00	\$ _____
(\$ _____) EA		
304.0900 WATER BOX ADJUST TO GRADE, RIGID BASE		
_____ Dollars	1.00	\$ _____
(\$ _____) EA		
304.1000 LOWER STREET SERVICE BOX		
_____ Dollars	47.00	\$ _____
(\$ _____) EA		
309.3000 Service Box and Cut-in Curb Stop (3/4" - 1")		
_____ Dollars	54.00	\$ _____
(\$ _____) EA		
310.6000 HYDRANT PAINTING		
_____ Dollars	12.00	\$ _____
(\$ _____) EA		

M25-6 Resurfacing

ITEM NUMBER AND DESCRIPTION	ESTIMATED QUANTITY	COMPUTED TOTALS
404.0000 PULVI-MILLING		
_____ Dollars	17,050.00	\$ _____
(\$ _____) SY		
405.0000 STRAIGHT CURB (VA-4)		
_____ Dollars	5,000.00	\$ _____
(\$ _____) LF		
408.0000 CIRCULAR CURB (10' RADIUS & OVER) (VA-4)		
_____ Dollars	265.00	\$ _____
(\$ _____) LF		
409.0000 CIRCULAR CURB (10" RADIUS & UNDER) (VA-4)		
_____ Dollars	265.00	\$ _____
(\$ _____) LF		
410.0000 CIRCULAR CORNER (WORCESTER STANDARD)		
_____ Dollars	186.00	\$ _____
(\$ _____) EA		
416.0000 CURB REMOVE AND RESET		
_____ Dollars	2,900.00	\$ _____
(\$ _____) LF		
422.1000 SUPERPAVE 9.5 MM LEVEL 2		
_____ Dollars	550.00	\$ _____
(\$ _____) TN		
422.2000 SUPERPAVE 12.5 MM LEVEL 2		
_____ Dollars	4,038.00	\$ _____
(\$ _____) TN		
424.0000 BITUMINOUS CONCRETE DRIVEWAY & VARIOUS AREA		
_____ Dollars	165.00	\$ _____
(\$ _____) TN		

M25-6 Resurfacing

ITEM NUMBER AND DESCRIPTION	ESTIMATED QUANTITY	COMPUTED TOTALS
430.0000 EXISTING BITUMINOUS CONCRETE DRIVEWAY REPAIR		
	Dollars	600.00 \$
(\$) SY		
432.0000 EXISTING BITUMINOUS CONCRETE SIDEWALKS REPAIR		
	Dollars	20.00 \$
(\$) SY		
435.0000 HOT POURED RUBBERIZED ASPHALT SEALER		
	Dollars	1,350.00 \$
(\$) LF		
438.0000 BITUMINOUS CONCRETE BERM MACHINE PLACED		
	Dollars	200.00 \$
(\$) LF		
440.0000 NEW CONCRETE SIDEWALK 4 INCH		
	Dollars	1,400.00 \$
(\$) SY		
441.0000 REPLACING BITUMINOUS CONCRETE SIDEWALK W/CONCRETE SIDEWALK 4 INCH		
	Dollars	990.00 \$
(\$) SY		
442.0000 CONCRETE SIDEWALK REPAIR		
	Dollars	730.00 \$
(\$) SY		
443.0000 REPLACING BITUMINOUS CONCRETE DRIVEWAY W/CONCRETE DRIVEWAY 6 INCH		
	Dollars	960.00 \$
(\$) SY		
446.0000 CONCRETE DRIVEWAY REPAIR		
	Dollars	310.00 \$
(\$) SY		

M25-6 Resurfacing

ITEM NUMBER AND DESCRIPTION	ESTIMATED QUANTITY	COMPUTED TOTALS
446.1000 CLASS B CONCRETE FOR ROADWAY BASE (3,500 P.S.I. 1-1/2 520)		
	Dollars	320.00 \$
(\$) CY		
447.0100 NEW BRICK SIDEWALKS AND DRIVEWAYS WITH GRAVEL BASE		
	Dollars	50.00 \$
(\$) SY		
447.0200 EXISTING BRICK SIDEWALKS AND DRIVEWAYS WITH GRAVEL BASE – REMOVE & RESET		
	Dollars	100.00 \$
(\$) SY		
448.0000 WORCESTER HIGHWAY MONUMENT		
	Dollars	11.00 \$
(\$) EA		
450.0000 BOUNDS, REMOVE & RESET		
	Dollars	7.00 \$
(\$) EA		
454.0000 WHEELCHAIR RAMP CEMENT CONCRETE - 6" THICK WITH DETECTABLE WARNING PANELS		
	Dollars	410.00 \$
(\$) SY		
456.0000 CONCRETE STEP (COMPLETE IN PLACE)		
	Dollars	9.00 \$
(\$) EA		
483.0000 REPLACING GAS BOX, GRAVEL BASE		
	Dollars	6.00 \$
(\$) EA		
485.0000 REMOVE AND RETAIN GAS BOX		
	Dollars	18.00 \$
(\$) EA		

M25-6 Resurfacing

ITEM NUMBER AND DESCRIPTION	ESTIMATED QUANTITY	COMPUTED TOTALS
486.0000 RETURN AND RESET GAS BOX		
	Dollars	13.00 \$
(\$) EA		
502.0000 4 INCH REFLECTORIZED YELLOW LINE (THERMOPLASTIC)		
	Dollars	200.00 \$
(\$) LF		
503.0000 12 INCH REFLECTORIZED WHITE LINE (THERMOPLASTIC)		
	Dollars	700.00 \$
(\$) LF		
520.0000 WARNING AND REGULATORY SIGNS		
	Dollars	9.00 \$
(\$) EA		
522.0000 TYPE "B" STREET NAME SIGNS		
	Dollars	7.00 \$
(\$) EA		
523.0000 TRAFFIC SIGN POLES		
	Dollars	14.00 \$
(\$) EA		
530.0000 POLE PAINTING		
	Dollars	8.00 \$
(\$) EA		
806.2000 2 INCH ELECTRICAL CONDUIT (FOOT)		
	Dollars	3,200.00 \$
(\$) LF		
810.3000 PULL BOX 12"X24" (SD 2.030) FOR SIGNAL CABLE		
	Dollars	17.00 \$
(\$) EA		

M25-6 Resurfacing

ITEM NUMBER AND DESCRIPTION	ESTIMATED QUANTITY	COMPUTED TOTALS
810.4000 PULL BOX 12"X12" (SD 2.031) FOR INTERCONNECTION CABLE		
	Dollars	8.00 \$
(\$) EA		
812.2000 LIGHT STANDARD FOUNDATION CONCRETE (EACH)		
	Dollars	17.00 \$
(\$) EA		
813.3200 CONDUCTOR #6 AWG (FOOT)		
	Dollars	6,300.00 \$
(\$) LF		
814.0000 REMOVE AND RESET STREET LIGHT POLE		
	Dollars	17.00 \$
(\$) EA		
821.0000 STREET LIGHT		
	Dollars	2.00 \$
(\$) EA		
900.0000 Lump Sum Reserve		
two hundred forty thousand five hundred seventy-two and xx / 100	Dollars	\$ 240,572.00
953.2020 SILT SACK		
	Dollars	43.00 \$
(\$) EA		

TOTAL BID PRICE INCLUDING CONTINGENCY

_____ Dollars and _____ Cents
(amount in words)

\$ _____
(amount in figures)

This proposal is based on provisions of the following addenda:

No. _____

No. _____

No. _____

No. _____

All amounts and totals given above will be subject to verification by the City. In case of variation between Unit Bid Price and Totals shown by the Bidder, the Unit Price written in words will be considered to be the bid.

The City reserves the right to reject any and all bids, wholly or in part, and to make awards in a manner deemed in the best interests of the City.

The above estimated quantities form an approximate statement of the extent of the work to be done, based upon the estimate of the Contracting Officer. The City does not expressly or by implication agree that the actual quantity of work will correspond therewith, but reserves the right to increase or decrease the quantity of any class or portion of the work, as may be deemed necessary by the Contracting Officer.