The City of WORCESTER

Administration & Finance – Purchasing Division
Christopher J. Gagliastro, MCPPO – Purchasing Director
455 Main Street, Room 201, Worcester, MA 01608
P | 508-799-1220
purchasing@worcesterma.gov

October 22, 2026

To All Bidders:

Subject: **Bid No. 8803-1-M7 – Generator Replacement – Union Station / WRA**

ADDENDUM NO. 3

To Whom It May Concern:

With reference to our bid request relative to the above subject, please refer to the changes/modifications/clarifications to the original proposal request.

GENERAL BID CLARIFICATIONS

1. None.

PROJECT MANUAL ITEMS

1. No changes.

DRAWING ITEMS

1. No changes.

The City of WORCESTER

Administration & Finance – Purchasing Division
Christopher J. Gagliastro, MCPPO – Purchasing Director
455 Main Street, Room 201, Worcester, MA 01608
P | 508-799-1220
purchasing@worcesterma.gov

CONTRACTOR QUESTIONS

1. Q: Is the building required to have a source of emergency power at all times? If so, please confirm that the City will be providing a temporary generator, to be connected via the proposed Camlock Connection at the Garage, to provide emergency power to the building during the period while the old generator is removed and the new permanent generator is being installed, and that the Prime bidder does not own any scope relating to this temporary generator, not shown on the plans.

   A: Prior to removing the existing 250KW roof top generator, the Contractor shall install the generator quick-connect panel, manual transfer switch, feeder from the generator quick-connect panel to the manual transfer switch, and feeder from the load side of the manual transfer switch to the junction box above ATS-S and ATS-E. Under a brief interruption of available emergency power, the Contract shall remove the feeder from the existing roof top generator in the junction box above ATS-S and ATS-E and connect the new feeder from the manual transfer switch. The Contractor shall provide a temporary 250 KW generator with associated fuel and connect it to generator quick-connect panel with the manual transfer switch in the temporary generator position while the roof top generator is being replaced. When the roof top generator has been replaced, new generator feeders have been installed to the manual transfer switch, and the new generator successfully tested, the manual transfer switch can be switched over to the new roof top generator and the temporary generator can be removed.

Bidders are requested to acknowledge and/or include this addendum with submission. All other terms, conditions and specifications remain unchanged.

Very truly yours,

Stephen R. McDonald
Assistant Purchasing Director