

**Flooring Replacement – Grove St Fire Station**  
**Bid#: 8393-M5**  
**Specifications**

**Worcester Fire Department**

141 Grove St  
Worcester, MA 01605

**SPECIFICATIONS FOR  
Flooring Repair**

at  
Grove St Fire Station  
141 Grove ST  
Worcester, MA 01605

**PART 1 – GENERAL**

**1.1 DESCRIPTION**

The Worcester Fire Department Grove St Station has a concrete apparatus floor that needs repair and sealing in the following areas:

Entire apparatus bay including entrance vestibule, four apparatus bays, one car bay and 3 adjacent small rooms. Approximately 6,000sq ft

**1.2 WORK INCLUDED**

- A. Level and prep the existing areas to repair any holes and ruts in the concrete, Install the new flooring according to manufacturer's specifications, as well as any other leveling and prep work, which may be needed.

**PART 2- PRODUCTS**

**2.1 MATERIALS**

- A. Product: 1/8" Eurothane Cement with MMA topcoat

**PART 3- EXECUTION**

**3.2 CLEANING AND PROTECTION**

- A. After completion, remove all trash and resultant material from the project and dispose of properly.

## **PART 4-SPECIAL CONDITIONS**

### **4.1 EXTRAS AND CHANGES**

- A. The repair and topcoat must not add more than ¼" to the floor height. This restriction is specific to fitting the apparatus in the apparatus bay.
- B. The bid shall be inclusive with no extras. The need for extra work or changes in the specifications will be at the determination of the Worcester Fire Department and will be submitted as a written work order to the Contractor. No extra work will be performed or changes made without a written work order from the Worcester Fire Department.
- C. The Contractor shall be responsible for protecting the Department's property and shall be solely responsible for the repair of any damage determined to have been caused by their actions during their performance of this work.
- D. The Contractor shall make the work area safe for Department staff who may be in the area.
- E. The Contractor shall maintain a full work force from start to completion and shall have a qualified foreman on the job at all times. The department may require the need to operate from the area with coordination of command staff to make operational adjustments as needed.
- F. The Contractor shall produce on demand any valid licenses necessary to operate in Worcester, MA. And must obtain any permits required.