

**SCHEDULE OF PRICES
CITY OF WORCESTER, MASSACHUSETTS
QUINAPOXET TRANSFER PIPELINE, CONTRACT 2**

ITEM NO.	ITEMS OF WORK	UNITS	ESTIMATED QUANTITY	UNIT PRICES BID		AMOUNTS**
				WORDS***	FIGURES	
1	Sand Borrow	CY	3,100			
2	Rock Excavation	CY	800			
3	Earth Excavation Below Grade	CY	800			
4	Crushed Stone	CY	800			
5	Gravel Borrow	CY	800			
6	Miscellaneous Concrete	CY	50			
7	2" Combination Air Valves	EA	5			
8	36" Butterfly Valves	EA	2			
9	6" Gate Valves	EA	8			
10	Precast Manholes	EA	14			

**SCHEDULE OF PRICES
CITY OF WORCESTER, MASSACHUSETTS
QUINAPOXET TRANSFER PIPELINE, CONTRACT 2**

ITEM NO.	ITEMS OF WORK	UNITS	ESTIMATED QUANTITY	UNIT PRICES BID		AMOUNTS**
				WORDS***	FIGURES	
11	Television Inspection	LF	1,900			
12	Pipe Cleaning	LF	1,900			
13	30" DR 25 C905 Fusible PVC Pipe (Sliplining)	LF	1,900			
14	30" DR 25 C905 PVC Pipe (Open Cut)	LF	2,100			
15	30" DR 25 C905 RJ PVC Pipe (Pump Station Road)	LF	2,300			
16	36" PC 250 Ductile Iron Pipe	LF	40			
17	6" PC 250 Ductile Iron Pipe	LF	40			
18	Additional Fittings	LBS	12,800			
19	Temporary Pavement	TON	800			
20	Permanent Pavement	TON	1,500			

**SCHEDULE OF PRICES
CITY OF WORCESTER, MASSACHUSETTS
QUINAPOXET TRANSFER PIPELINE, CONTRACT 2**

ITEM NO.	ITEMS OF WORK	UNITS	ESTIMATED QUANTITY	UNIT PRICES BID		AMOUNTS**
				WORDS***	FIGURES	
21	Gravel Base for Pavement	LF	2,064			
22	Erosion Control	LS	1			
23	Site Restoration/Vegetation Restoration	LS	1			
24	Site Restoration – 1567 Main Street	LS	1			
25	Traffic Control Devices	LS	1			
26	SIPP Lining	LF	230			
27	Licensed Professional Land Surveyor	LS	1			
28	Fencing and Gates	LS	1			
29	30" DR 25 PC C905 Fusible PVC Pipe - Install Only	LF	444			
30	Pre and Post Condition Survey	EA	2			

**SCHEDULE OF PRICES
CITY OF WORCESTER, MASSACHUSETTS
QUINAPOXET TRANSFER PIPELINE, CONTRACT 2**

ITEM NO.	ITEMS OF WORK	UNITS	ESTIMATED QUANTITY	UNIT PRICES BID		AMOUNTS**
				WORDS***	FIGURES	
31	Tree Removed (City) - Diameter Under 2 Feet	EA	5			
32	Tree Removed (City) - Diameter 2 Feet and Over	EA	5			
33	Tree Removed (Town) - Diameter Under 2 Feet	EA	5			
34	Tree Removed (Town) - Diameter 2 Feet and Over	EA	5			
35	Allowance for Worcester Emergency Pipe Use	LS	1	<i>Three Hundred Thousand Dollars and no/100</i>	<i>\$300,000.00</i>	<i>\$300,000.00</i>
36	Allowance for Electrical Work	LS	1	<i>Five Thousand Dollars and no/100</i>	<i>\$5,000.00</i>	<i>\$5,000.00</i>
37	Allowance for Price Adjustment*	LS	1	<i>Four Hundred Thousand Dollars and no/100</i>	<i>\$400,000.00</i>	<i>\$400,000.00</i>
ESTIMATED TOTAL CONSTRUCTION COST						

IMPORTANT:

- * The Bidder is required to submit pipe materials quote(s) for Items 13 thru 17 as part of the bid package as a baseline cost to use this allowance.
- ** The Bidder is requested to fill in computed "Amounts." In case of a discrepancy between Unit Prices Bid written in *words* and the Unit Prices Bid written in *figures*, the Unit Prices Bid written in words will govern. In case of a discrepancy between the Unit Prices *Bid* and *Amounts*, the Unit Prices *Bid* will govern.
- *** Write in *words* the lump sum bid in the column provided for Unit Prices Bid in words, and write in *figures* the lump sum bid in the column headed "Amounts."

The Contractor agrees that he will start work no later than 10 calendar days after the date of the Notice to Proceed. All work shall be completed within 548 consecutive calendar days.